

BOSTON DOOR COMPANY™

35 Inman St. G

Cambridge MA, 02139

(888) 497-6295

info@bostondoorcompany.com

PROPOSAL

Date: May 18, 2021

Natural Finish Restoration of Three (3) Sets of Front Doors

Project Location:

990, 1000 Centre St.
Jamaica Plain,
(Adams Arboretum)

Customer Information

Reggie Thomas
Evergreen Management

1603 703 8160
rthomas@evergreenmgt.com



BOSTON DOOR COMPANY™

35 Inman St. G
Cambridge MA, 02139
(888) 497-6295
info@bostondoorcompany.com

	Exterior Front Doors -990 Centre Street
	Exterior Front Doors -990 Centre Street #3
(No corresponding image)	Exterior Front Doors -1000 Centre street

BOSTON DOOR COMPANY™

35 Inman St. G

Cambridge MA, 02139

(888) 497-6295

info@bostondoorcompany.com

SCOPE OF WORK	
Exterior Set of Doors-990 center street	-
Exterior Set of Doors Natural Finish Restoration Exterior: Complete abatement of current finish Repair any visible wood damage Prep the exterior of the doors for natural oil finish. Finish: Natural Oil Varnish: Epiphanes (3-5 coats) Interior: Clean up the interior Hardware*** Perform Hardware Maintenance Repair the broken hinge, or find an exact replacement Reinstall the hardware Reinstall the doors assuring full function Materials, Supplies and Expenses Total	
Exterior Set of Doors -(990 #3 center street) Exterior Set of Doors Natural Finish Restoration Exterior: Complete abatement of current finish Repair any visible wood damage Prep the exterior of the doors for natural oil finish. Finish: Natural Oil Varnish: Epiphanes (3-5 coats) Interior: Clean up the interior, Hardware Perform Hardware Maintenance Replace any hardware if necessary (not expected) Reinstall the hardware Reinstall the doors assuring full function Materials, Supplies and Expenses Total	
Exterior Set of Doors -(1000 center street)	
SCOPE Exterior Set of Doors Natural Finish Restoration Exterior: Complete abatement of current finish Repair any visible wood damage Prep the exterior of the doors for natural oil finish. Finish: Natural Oil Varnish: Epiphanes (3-5 coats) Interior: Clean up the interior Refinish the Surrounding Woodwork Clean up the interior, and Prep the current finish for topcoat Topcoat the interior side of the doors Finish: Natural Oil Varnish Hardware Perform Hardware Maintenance Replace any hardware if necessary (not expected) Reinstall the hardware, and doors assuring full function Materials, Supplies and Expenses Total	
Quote Proposed	\$20,000.00

BOSTON DOOR COMPANY™

35 Inman St. G

Cambridge MA, 02139

(888) 497-6295

info@bostondoorcompany.com

BASIC TERMS

Project duration

Scope of work listed above will take approximately 2-3 months depending on weather elements during the finishing schedule. The total duration of the project may be accelerated by overlapping the on-site restoration projects.

Project Logistics

The work is to be performed on-site, and not interfere with day-day activities on the premises. Specific logistic details are to be firmed upon approval of this proposal.

Payment Schedule

50% first payment (deposit)

25% at about ½ way point in the project

25% upon completion of the project

We look forward to doing business with you, and making your Front Doors look and function like new again.

Sincerely,

-Seva

Sam Tsodokov

617 233-2446

Boston Door Company

Work: (888) 497-6295

info@bostondoorcompany.com